

**City of Fruita
Bid Schedule**

Reed Park Improvements Project

<u>No.</u>	<u>Referenced Spec. Section</u>	<u>Item</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Extension</u>
1	Special Prov.	Mobilization & Demobilization	LS	1		
2	Special Prov.	Construction Surveying	LS	1		
3	Special Prov.	Material Testing	LS	1		
4	312270	Temp. Erosion and Sedimentation Control/Stormwater Mgmt.	LS	1		
5	Special Prov.	Traffic Control	LS	1		
6	311000	Site Clearing	LS	1		
7	312000	Earth Moving	LS	1		
8	Special Prov.	Remove/Dispose of Existing Asphalt (Full-Depth)	SY	70		
9	Special Prov.	Remove/Dispose of Existing Concrete (Includes Wall)	SF	7000		
9A	Special Prov.	Remove/Dispose of Existing Concrete (Add Alternate)	SF	900		
10	Special Prov.	Remove/Dispose of Existing Planting Area	SF	17000		
10A	Special Prov.	Remove/Dispose of Existing Planting Area (Add Alternate)	SF	7100		
11	Special Prov.	Remove/Dipose of Existing Tree	Each	8		
11A	Special Prov.	Remove/Dipose of Existing Tree (Add Alternate)	Each	3		
12	Special Prov.	Remove/Dispose of Existing Bathroom Facility/Foundation	LS	1		
13	Special Prov.	Remove/Dispose of Existing Playground Equipment	LS	1		
14	Special Prov.	Remove/Salvage Merry-Go-Round	LS	1		
15	Special Prov.	Remove/Dispose of Existing Playground Mulch	LS	1		
16	Special Prov.	Cap/Remove/Abandon Existing Gas Service	LS	1		
17	Special Prov.	Cap/Remove/Abandon Existing Water Tap/Line/Meter	LS	1		
18	Special Prov.	Cap/Remove/Abandon Existing Sewer Service Line	LS	1		
19	Special Prov.	Remove/Dispose of Existing Horseshoe Pits	LS	1		
20	Special Prov.	Remove/Fill Existing Drain Sump	LS	1		
21	Special Prov.	Remove/Dispose of Existing Water Fountain	LS	1		
22	Special Prov.	Remove/Dispose of Existing Chain Link Fence	LF	130		
23	329300	Catalpa speciosa (Western Catalpa)	Each	4		
23A	329300	Catalpa speciosa (Western Catalpa) (Add Alternate)	Each	1		
24	329300	Morus alba 'fruitless' (Fruitless Mulberry)	Each	4		
25	329300	Comus sericea (Red Twig Dogwood)	Each	73		
26	329300	Boeteloua gracilis (Blue Grama)	Each	616		
26A	329300	Boeteloua gracilis (Blue Grama) (Add Alternate)	Each	376		
27	329300	Nepeta 'Little Trudy' (Catmint 'Little Trudy')	Each	80		
28	329300	Perovskia atriplicifolia (Russian Sage)	Each	233		
28A	329300	Perovskia atriplicifolia (Russian Sage) (Add Alternate)	Each	68		
29	329200	Buffalo Brand Dura- Turf Plus	SF	8372		
30	015639	Temporary Tree and Plant Protection	LS	1		
30A	015639	Temporary Tree and Plant Protection (Add Alternate)	LS	1		
31	044400	Boulder Type A	Each	8		
32	044400	Boulder Type B	Each	10		
33	116800	Horseshoe Pit	Each	7		
34	321313/Special Provisions	Pedestrian Cast-in-Place Concrete Paving	SF	6800		
34A	321313/Special Provisions	Pedestrian Cast-in-Place Concrete Paving (Add Alternate)	SF	5450		
35	321313/Special Provisions	Vehicular Cast-in-place Concrete Paving	SF	1000		
35A	321313/Special Provisions	Vehicular Cast-in-place Concrete Paving (Add Alternate)	SF	360		
36	CDOT M-608-1	Vehicular Ramp	Each	1		
37	CDOT M-608-1	Pedestrian Ramp	Each	1		
38	Special Prov.	Drain Pan	LF	110		
39	Special Prov.	Curb & Gutter	LF	155		
40	Special Prov.	Sidewalk Chase	Each	2		
41	Special Prov.	Park Electrical System	LS	1		
42	265600	Light Type 1	Each	3		

**City of Fruita
Bid Schedule
Reed Park Improvements Project**

<u>No.</u>	<u>Referenced Spec. Section</u>	<u>Item</u>	<u>Unit</u>	<u>Quantity</u>	<u>Unit Cost</u>	<u>Extension</u>
43	323300	Bench Type 1	Each	6		
43A	323301	Bench Type 1 (Add Alternate)		4		
44	323300	Picnic Table Type 1	Each	4		
45	323300	Bike Rack	Each	1		
46	Special Prov.	Trash Bin	Each	1		
47	323119	Decorate Metal Fence	LF	150		
48	321216/Special Provisions	Asphalt Pavement	SY	200		
49	321540	Crushed Stone Surfacing	SF	5000		
50	321363	Painted Pavement Markings	LF	850		
51	321363	Thermoplastic Pavement Markings	Each	4		
52	328433	Irrigation-Design/Build	LS	1		
52A	328433	Irrigation-Design/Build (Add Alternate)	LS	1		
53	334600	4" Perforated HDPE Playground Underdrain pipe	LF	132		
54	334600	6" Perforated PVC Underdrain Pipe	LF	60		
55	334100	6" PVC Storm Sewer Pipe	LF	366		
56	333113	4" SDR-35 PVC Sanitary Sewer Service Pipe	LF	55		
57	333113	4" Sanitary Sewer Cleanouts	Each	2		
58	334100	4" Storm Drain Cleanouts	Each	9		
59	334100	6" Storm Drain Cleanouts	Each	5		
60	334100	Storm Drain Inlets	Each	9		
61	221113	1-1/2" Copper Water Service	LF	145		
62	Construction Plans Sheets C4-00 Through C4-03	Stormwater Pump System	LS	1		
63	S. Shelter Drawings (Blythe Sheets)	Shelter/Restroom (Complete in Place)	LS	1		
64	Special Prov.	Northern Shelter (Install Only)	LS	1		
65	S/W Park Drawings/Specs.	Skate/Wheel Park (Complete in Place)	LS	1		
66	Special Prov.	Contingency/Force Account	LS	1	\$ 200,000.00	\$ 200,000.00
Total Base Bid Amount:						

Company Name: _____

By: _____

Signature: _____

Date: _____